



WELL LOG

OPERATOR: PARRISH OIL COMPANY

WELL NAME: HAYS "A" #5 LOCATION: 450' N NW SW NW

COUNTY: HODGEMAN STATE: KANSAS

WELL COMMENCED: DEC 27 '74 WELL COMPLETED: JAN 6 '75

ELEVATION: 2351 KB TOTAL DEPTH: 4615

PRODUCTION: DRY & ABANDONED RIG NO: 1

CASING - 8-5/8": 12 JTS 476.33' W/325 SX POZMIX 2% GEL 3% CA CL

5-1/2": .....

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	840	SHALE & RED		
840	1085	RED BED		
1085	1265	SAND		
1265	1591	RED BED		
1592	1640	ANHYDRITE		
1641	2200	SHALE	1° 1850'	
2200	4130	LIME & SHALE	1° 2493'	
4130	4615	LIME		DST #1 4585'-4600' OPEN 30 SI 60 REC 20' OIL CUT MUD FBHP 150# IFP 46# FFP 46#
	4615	RTD		
				DST #2 4585'-4615' OPEN 20 SI 60 OP 60 SI 90 REC 3300' SALT WATER FBHP 1451# IBHP 1451# FFP 1451# IFP 752#

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.


By G. F. Galloway

G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 10th day of January, 1975.

MY COMM. EXP. DEC. 7, 1975

Phyllis Buchanan  
PHYLIS BUCHANAN - NOTARY PUBLIC



RECEIVED  
STATE CORPORATION COMMISSION

12-19/5

CONSERVATION DIVISION  
Wichita, Kansas