


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgman County, Sec. 30 Twp. 22S Rge. (E) 23 (W)  
Location as "NE/CNW/SW" or footage from lines 430' FNL, 1360' FWL NW/4  
Lease Owner Parrish Oil Company  
Lease Name Hays "A" Well No. SWDW  
Office Address 714 4th Natl Bk. Bldg. Wichita, 68202  
Character of Well (completed as Oil, Gas or Dry Hole) Salt water disposal  
Date well completed 5-7 1960  
Application for plugging filed 2-20 1975  
Application for plugging approved Verbal 2-20 1975  
Plugging commenced 2-20 1975  
Plugging completed 2-20 1975  
Reason for abandonment of well or producing formation Lease abandoned

If a producing well is abandoned, date of last production --- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Clarence Thomas  
Producing formation Cedar Hills Depth to top 1110 Bottom 1320 Total Depth of Well 1327 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cedar Hills sand	water	1110	1320	4 1/2	1322	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran 20 jts tubing  
Pumped 30 sacks cement, plug from 1017 to 1327  
Ran 6 jts. tubing  
Pumped 20 sacks cement, plug from 0 to 220'  
Pulled tubing.

Plugging completed 5:30 PM 2-20-75

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1975  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Chase Well Service License No. 467  
Address 5221 Ridgeway, Great Bend, 67530


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Lloyd K. Parrish Jr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Lloyd K. Parrish Jr

714 4th Natl. Bk. Bldg. Wichita (Address)

SUBSCRIBED AND SWORN to before me this 24th day of February 1975

Frances E. Barham  
Notary Public.

My commission expires April 20, 1975



15.083-19022-0000

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

Hays SWD No. 1  
1360' from West line, and  
430' from North line  
NW/4 Sec. 30-22S-23W,  
Hodgeman County, Kansas

Total Depth: 1327'

Commenced: 5-7-60 Completed: 5-8-60

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Casing record: Four and one-half inch pipe set at 1322' and cement circulated to surface using 500 sacks.

Figures indicate bottom of formations:

Clay, sand & shale	295'
Shale & sand	1110'
Sand	1320'
Shale	1327'
Total Depth	1327'

RECEIVED  
STATE CORPORATION COMMISSION

FEB 25 1975

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By *K. B. Bone*  
Petroleum Engineer

Subscribed and sworn to before me this 13th day of May, 1960.

My Commission Expires:

July 7, 1962

*Moná L. Latier*  
Moná L. Latier, Notary Public