


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Hodgeman County. Sec. 26 Twp. 22 Rge. 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Jensen G Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/1/55 19
Application for plugging filed 9/31/55 19
Application for plugging approved 8/31/55 19
Plugging commenced 9/1/55 19
Plugging completed 9/1/55 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5031 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	305	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it to the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Layed down drill pipe. Filled hole with heavy mud to 300'. Set 1st plug, using 1/4 sack hulls and 20 sacks cement. Filled hole with heavy mud to 35'. Set 2nd plug using 1/4 sack hulls and 10 sacks cement. Top plug tied with wire.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address 420 West Douglas, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Robert B. Snyder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Snyder
(Address) _____

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1955

My commission expires 1-30-57

Margie Cooper
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.
SEP 15 1955
9-15-55
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEE 26 T 22 R 23 W
BOOK PAGE 147 LINE 30

Trans Era Petroleum, Inc.
Jensen "G" #1

SW SW SE 26-22-23
Hodgeman County, Kansas

Total Depth: 5031'

Comm: 8/12/55
Comp: 9/1/55

Casing
8 5/8 set @ 305

Cement
200 sacks of Bulk

FORMATION	DEPTH
Clay	35
Sand & clay	60
Shale & shells	305
Shale & Redbed	820
Anhydrite	840
Shale & Redbed	1430
Shale & Gyp	1460
Sand & Shale	1490
Shale	1780
Shale & salt	1890
Shale & shells	2200
Shale & Lime	3165
Shale & shells	3251
Lime & shale	3835
Lime	3980
Lime & shale	4033
Lime	4399
Lime & shale	4495
Mississippi	4510
Cherty lime	4615
Lime	4642
Lime & chert	4699
Lime, chert & dolomite	4730
Lime	4845
Lime, sand & cherty shale	4859
Chert & lime	4895
Shale & lime	5002
Arbuckle	5031

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1955
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

Robert B. Smalley

Subscribed and sworn to before me this 12th day of September, 1955.

Margie Cooper
Notary Public

My commission expires: 1-30-57

PLUGGING
WELL SEC 26 T 22 R 23 W
BLOCK PAGE 147 LINE 26