

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20928-0000

LEASE NAME Marvin

WELL NUMBER M-1

330' Ft. from ^N Section Line

330' Ft. from E Section Line

SEC. 27 TWP. 22 SRGE. 23W (E) or (W)

COUNTY Hodgeman

Date Well Completed _____

Plugging Commenced 9-3-97

Plugging Completed 9-8-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399 Garden City, Kansas 67846

PHONE (316) 274-2963 OPERATORS LICENSE NO. 4058

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Mike Meyeres (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4583'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	301'	none
				5-1/2"	4568'	320'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 4498' and 5 sacks cement. Shot @1600', 1000', 700', spotted 80 sks. cement and 10 sks. gel, shot loose @320', spotted 50 sks. of cement, pulled pipe out, ran 1 it. back in and circulated 10 sacks cement. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

9-17-97

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 97

[Signature]
Notary Public

My Commission Expires: _____



RECEIVED
KANSAS CORPORATION COMMISSION
1997 SEP 17 10 41 AM

BERGMAN DRILLING, INC.

DRILLERS LOG

Re: Marvin M. # 1
NE NE NE Section 27-22S-23W
Hodgeman County, Kansas

Elevation: 2308GL

OPERATOR: Bergman Oil Company

CONTRACTOR: Bergman Drilling, Inc.

COMMENCED: October 13, 1981

COMPLETED: October 23, 1981

TOTAL DEPTH: 4583' Set 8 5/8" @ 301.71 w/175 sx.

0	63	Suerace
63	288	Clay & Benite & Shale
288	1610	Shale & Shells w/ clay
1519	1548	Anhydrite
1610	2057	Lime & Shale
2306	2497	Lime & Shale
2497	2620	Lime & Shale
2620	2735	Lime & Shale
2735	2826	Lime & Shale
2826	2938	Lime & Shale
2938	3095	Lime & Shale
3095	3243	lime & Shale
3243	3256	Lime & Shale
3256	3460	Lime & Shale
3460	3592	Lime & Shale
3592	3835	Lime & Shale
3835	3944	Lime & Shale
3944	4031	Lime & Shale
4031	4143	Lime & Shale
4143	4240	Lime & Shale
4240	4310	Lime & Shale
4310	4385	Lime & Shale
4385	4450	Lime & Shale
4450	4513	Lime & Shale
4513	4567	Lime & Shale
4567	4583	Lime & Shale
4583		RTD


RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1981


CONSERVATION DIVISION
Wichita Kansas

Set 5 1/2" @ 4568' w/100 sx.

We certify that the above and foregoing to be true and correct copy of the Drillers Log on the # 1 Marvin M, located in Hodgeman County Kansas as revealed by the records of Bergman Drilling, Inc.


Harold I. Bergman

Subscribed and sworn to before me this
26th day of October, 1981


Alma A. Neises, Notary Public

My commission Expires May 31, 1982