

15-145-20656-0006


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 22S Rge. 17WE/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
S/2 SE SE

Lease Owner Tomlinson Oil Company
Lease Name FRICK Well No. 1
Office Address 200 W. Douglas, Suite 1030, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed March 21 1980
Application for plugging filed (verbally) March 21 1980
Application for plugging approved (verbally) March 21 1980
Plugging commenced March 21 1980
Plugging completed March 21 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4200'

Set 1st plug at 540' with 50 sacks
2nd plug at 240' with 40 sacks
3rd plug at 40' solid bridge with 10 sacks
5 sacks in the rathole.

Cemented with 50/50 posmix, 4% gel.
Job was complete at 9:00 a.m., 03-02-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jerry A. Langrehr, Exec. Vice-Pres. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1980



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1980
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Frick #1
 LOCATION: S/2 SE SE, Section 34-22S-17W,
 Pawnee County, Kansas
 SPUD DATE: February 20, 1980
 COMPELTION DATE: March 02, 1980

0	371	Sand and clay
371	1568	Red bed and shale
1568	1766	Shale
1766	4200	Lime and shale
	4200	Rotary Total Depth

Spud hole at 12:15 p.m., February 20, 1980. Drilled 265' of 12 1/4" hole. Ran 6 joints of 8-5/8" casing, consisting of 3 joints of new 8-5/8"-24# casing and 3 joints of 8-5/8" used 28# casing. (Talley 255'). Set at 265' with 225 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 5:15 p.m., February 20, 1980.

T.D. 4200'. Set 1st plug at 540' with 50 sacks, 2nd plug at 240' with 40 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 4% gel. Job was complete at 9:00 a.m., March 02, 1980.

SAMPLE TOPS:

Anhydrite 1098'
 B/Anhydrite 1118'

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 10 1980

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas

Jerry A. Langrehr, Executive Vice-President, of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Frick #1, S/2 SE SE, Section 34-22S-17W, Pawnee County, Kansas.

ABERCROMBIE DRILLING, INC.

BY

Jerry A. Langrehr
 Jerry A. Langrehr
 Executive Vice-President

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 6th day of March, 1980.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.