

WELL PLUGGING RECORD

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate well correctly on above  
Section Plat

Pawnee County. Sec. 34 Twp. 22 Rge. 17 (X) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Drilling & Exploration Co., Inc.  
Lease Name XXXX Pyle Well No. # 1  
Office Address 811 Union Center Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed yes \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved yes \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-22-60 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6-28-60 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4253' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 5 1/2" |        | 3,143'     |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging commenced 6-22-60. Plugging completed 6-28-60.  
Measured into total depth, 4253'. Plugged off bottom: Sanded back up hole to 4110' and dumped 5 sacks of cement. Took tention on pipe. Worked and shot casing free at 3126'. Built rack and slide. Pulled and laid down casing. Pumped in 38 barrels of mud to stop water flow from Dakota formation. Squeezed the well with 70 sacks of cement.

7-6-60  
RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1960

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co. Wichita, Kansas  
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Fred W. Mohr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred W. Mohr  
Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of June, 19 60

My commission expires December 8th, 1963

Kayann Jenkins Notary Public.

PYLES NO. 1 WELL

LOCATION: SW/4 SW/4 SW/4  
Section 34-22S-17W  
Pawnee County, Kansas

SPUDDED: 9-20-54  
COMPLETED: 10-5-54

OWNER: Twin Oil Corporation  
2706 Republic National Bank Building  
Dallas, Texas

CONTRACTOR: Birmingham-Bartlett Drilling Co.  
300 Kaufman Building  
Wichita 2, Kansas

SURFACE CASING: 8-5/8" 24# casing cemented at 252'  
with 225 sacks cement and 3 cc.

OIL STRING: 5-1/2" J-55 14# casing cemented at 4251'  
with 150 sacks cement

L O G

(Figures indicate bottom of formation)

|     |      |                         |
|-----|------|-------------------------|
| 0 - | 110  | Surface sand and clay   |
|     | 252  | Shale, lime shell       |
|     | 540  | Shale and red bed       |
|     | 680  | Sand                    |
|     | 940  | Shale and shells        |
|     | 1080 | Shale, sand and red bed |
|     | 1100 | Anhydrite               |
|     | 1955 | Shale and shells        |
|     | 2145 | Broken lime shale       |
|     | 2370 | Lime and shale          |
|     | 2410 | Sandy lime              |
|     | 2515 | Shale and shells        |
|     | 2675 | Lime and shale          |
|     | 3315 | Shale and shells        |
|     | 3475 | Lime                    |
|     | 3535 | Shale and lime          |
|     | 3590 | Lime                    |
|     | 3729 | Lime and shale          |
|     | 3950 | Lime                    |
|     | 3995 | Lime and shale          |
|     | 4055 | Lime                    |
|     | 4134 | Lime and shale          |
|     | 4145 | Shale                   |
|     | 4155 | Shale and chert         |
|     | 4180 | Shale                   |
|     | 4235 | Shale and chert         |
|     | 4253 | Shale and lime          |
|     | 4253 | Total Depth             |

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 11 1960

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Pyles No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me  
this 11th day of October, 1954.

Vivian L. Unger  
Notary Public

My commission expires November 29, 1954