

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 34 Twp. 22 Rge. 17 (E) (W)
Location as "NE/CNW%SW%" or footage from lines C SE SW SE
Lease Owner Drilling & Exploration Co., Inc.
Lease Name Wyman Well No. # 2
Office Address 811 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes 19____
Application for plugging approved yes 19____
Plugging commenced 6-28-60 19____
Plugging completed 7-6-60 19____
Reason for abandonment of well or producing formation _____

Correct

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4241' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,150'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 6-28-60. Plugging completed 7-6-60. Measured into total depth, 4241'. Plugged off bottom: Sanded back from 4241' to 4120' and dumped 5 sacks of cement. Worked and shot casing. Shot 5 1/2" casing at 3,150'. Worked pipe, not free. Spotted 38 barrels of oil. Worked pipe free. Built rack and slide. Pulled and laid down casing. Plugged well with 38 barrels of mud and 70 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 1960.

December 8th, 1963
My commission expires _____
Kayann Jenkins Notary Public.



Re



SE SW SE

C. WYMAN NO. 2 WELL

LOCATION:

SE/4 SW/4 SE/4 *CORRECT*
 Section ~~34-22S-17W~~
 Pawnee County, Kansas

SPUDED: 10-21-55

COMPLETED: 11-3-55

OWNER:

Drilling and Exploration Company, Inc.
 461 San Jacinto Building
 Houston 2, Texas

CONTRACTOR:

Birmingham-Bartlett Drilling Co.
 300 Kaufman Building
 Wichita 2, Kansas

SURFACE CASING:

8-5/8" 24# casing cemented at 245'
 with 200 sacks cement and 3 c. c.

OIL STRING:

5-1/2" 15.5# casing cemented at 4239'
 with 150 sacks cement.

LOG

(Figures indicate bottom of formation)

0	75	Sand
	245	Shale and clay
	425	Shale and sand
	1095	Sand, shells and red bed
	1115	Anhydrite
	1920	Shale and shells
	3010	Shale and lime
	3110	Shale and shells
	3395	Lime and shale
	3465	Lime
	3745	Lime and shale
	3990	Lime
	4060	Lime and shale
	4104	Lime
	4150	Conglomerate
	4239	Cherty conglomerate
	4239	Rotary total depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 11 1960
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the C. Wyman No. 2 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
 this 7th day of November, 1955.

Beverly Larson

Notary Public

My commission expires October 2, 1958.