


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
213 North Market, Insurance Bldg.
Wichita, Kansas

Pawnee County. Sec. 34 Twp. 22 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Drillers & Exploration Co., Inc.
Lease Name Wyman Well No. # 1
Office Address 811 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes 19____
Application for plugging approved yes 19____
Plugging commenced 6-14-60 19____
Plugging completed 6-22-60 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,334'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 6-14-60. Plugging completed 6-22-60.
Measured into total depth, 4260'. Plugged off bottom. Pushed plug to 4140' and dumped 10' of gravel and 5 sacks of cement.
Worked and shot casing. Shot 5 1/2" casing at 2334'. Worked casing free. Built rack and slide. Pulled and laid down casing. Dakota formation flowed and we put in 5 1/2" swedge to shut off flow.
Plugged well. Pumped in 38 barrels of mud and squeezed the well with 70 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling 6-28-60
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Fred W. Mohr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred W. Mohr
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 60.

My commission expires December 8th, 1963
Kayann Jenkins Notary Public.

RECEIVED
MAR 8 1955

15.145.01313-0000

PRODUCTION DEPT.

C. WYMAN NO. 1 WELL

LOCATION: Center of SE/4 SE/4 SW/4 Section 34-22S-17W Pawnee County, Kansas
 SPUNDED: 2-9-55
 COMPLETED: 2-21-55

OWNER: Drilling and Exploration Company, Inc. 461 San Jacinto Building Houston, Texas

CONTRACTOR: Birmingham-Bartlett Drilling Co. 300 Kaufman Building Wichita 2, Kansas

SURFACE CASING: 8-5/8" 24# casing cemented at 255' with 225 sacks cement and 3 cc.

OIL STRING: 5-1/2" 15.5# set at 4257' with 150 sacks cement.

LOG

(Figures indicate bottom of formation)

0	-	75	Sand and clay
		580	Shale and shells
		700	Sand
		1105	Shale, red bed and sand
		1135	Anhydrite
		1685	Shale and shells
		2665	Lime and shale
		2835	Shale, lime and shell
		3385	Shale and shells
		3445	Lime and shale
		3485	Lime
		3725	Lime and shale
		4060	Lime
		4108	Lime and shale
		4185	Lime
		4230	Cherty lime and shale
		4260	Chert and shale
		4260	Rotary Total Depth

RECEIVED
STATE GEOLOGICAL COMMISSION
AUG 11 1960
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the C. Wyman No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me this 23rd day of February, 1955.

Beverly Larson
Notary Public

My commission expires October 2, 1958.

One copy to Tom. Walker
3/17/55

1 copy sent to Mackart, Phillips & Ketchum
7/11/55

1 copy sent to Dallas Co. for Francis & Nathan Allen. 7/11/55