


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitt Building  
Wichita, Kansas

Pawnee County, Sec. 3 Twp. 22 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name BALDWIN A Well No. 4  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 25, 1953  
Application for plugging filed February 4, 1955  
Application for plugging approved February 6, 1955  
Plugging commenced March 9, 1955  
Plugging completed March 9, 1955  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3874 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	974'	
				5-1/2"	3872'	2620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand to 3860'.  
Set 1st plug 3/5 sx cement at 3860'.  
Filled hole with 25 sx mud to 320'.  
Set 2nd plug at 320' w/100 sx cement (Halliburton)  
Filled to top of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 12 1955  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Jayhawk Casing Pulling Company,  
Address Russell, Kansas.

STATE OF Kansas COUNTY OF Sedgwick SS.  
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of March, 19 55

Helma L. Stinson  
Notary Public.

My commission expires September 24, 1956.

**PLUGGING**  
FILE SEC 3 T22 R 16W  
BOOK PAGE 95 LINE 31

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation.  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: BALDWIN A #4  
 LOCATION: NE NW NW, Sec. 3-22-16  
 Pawnee County, Kansas.  
 COMMENCED: September 15, 1953  
 COMPLETED: September 25, 1953

0	100	Sand & Gravel
100	250	Sand, gravel & clay
250	420	Clay and shale
420	495	Sand
495	559	Shale & red bed
559	850	Red bed & shale
850	973	Shales sand & shells
973	1040	Anhydrite & shale
1040	1200	Sand & shaled shells
1200	1540	Shale & shells
1540	1840	Shaled lime shells
1840	3692	Shale & lime
3692	3742	Lime
3742	3874	Lime and shale
	3874	Rotary Total Depth

Set 8-5/8" surface casing at 973' with 450 sacks Pozmix cement

Set 5-1/2" casing at 3872' with 150 sacks cement.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the BALDWIN A #4 NE NW NW, Sec. 3-22-16, Pawnee County, Kansas, as reflected by the records of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

*Gordon L. Koelling*  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of September, 1953.

*William L. Stencamp*  
 Notary Public

My commission expires September 24, 1956.

**PLUGGING**  
 FILE SEC 3 T22R 16W  
 BOOK PAGE 96 LINE 21

RECORDED  
 DIVISION  
 Kansas