

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
860 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 3 Twp. 22 Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Fred Nixon et. al
Lease Name Buster Well No. 1
Office Address 10 Linden Drive, Forrest Hills, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 25 19 53
Application for plugging filed Oct. 25 19 53
Application for plugging approved Oct. 25 19 53
Plugging commenced Oct. 25 19 53
Plugging completed Oct. 25 19 53
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1065' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1006'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Layed down drill pipe, cemented with 20 sacks of cement at 200', Filled surface pipe with mud. Set 10 sacks cement plug at 40'.

10-28-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 53

John W. ...
Notary Public.

My commission expires September 17, 1957

PLUGGING
FILE SEC 3 T 22 R 16 W
BOOK PAGE 128 LINE 21

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG-----BUSTER #1

Location: NE NE SW Sec. 3, T. 22, R. 16, Pawnee County, Kansas

OWNER: Fred Nixon et. al
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company
 CABLE TOOL CONTRACTOR:

Commenced: 10-12-53 (w.r.)
 (w.c./t)
 Completed: 10-25-53 (w.r.)
 (w.c./t)

Total Depth: 4065'

LOG

0- 325	Surface Clay, Shale, & Shells
325- 440	Shale
440- 590	Sand & Shale
590- 995	Shale & Red Bed
995-1005	Anhydrite
1005-1405	Shale & Red Bed
1405-1735	Shale
1735-2110	Lime
2110-2435	Lime & Shale
2435-2555	Lime
2555-2865	Shale
2865-2975	Lime
2975-3130	Shale & Lime
3130-3815	Lime
3815-3865	Shale & Lime
3865-3905	Conglomerate & Viola
3905-3940	Viola
3940-3955	Simpson Shale
3955-4015	Shale
4015-4033	Simpson
4033-4065	Arbuckle

CASING RECORD

Ran 1006' of 8-5/8" casing, cemented with 450 sacks of bulk cement.

PRODUCTION

Dry and Abandoned

RECEIVED
 OCT 20 1953

PLUGGING
 FILE SEC 3 T. 22 R. 16 W
 PAGE 138 LINE 21