


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas



PAWNEE County, Sec. 35 Twp. 22 Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner HILTON DRILLING COMPANY, INC.
Lease Name REDETZKE Well No. 2
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed DECEMBER 19 55
Application for plugging filed JUNE 23 19 59
Application for plugging approved JUNE 26 19 59
Plugging commenced JULY 12 19 59
Plugging completed JULY 18 19 59
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production FEBRUARY 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT - ST. JOHN, Ks.
Producing formation CONGLOMERATE Depth to top Bottom Total Depth of Well 4267 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	NONE
				5-1/2"	4213'	3030'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED BACK WITH SAND FROM 4196 TO 4120', MIXED AND DUMPED
5 SX. CEMENT FROM 4120' TO 4080', PULLED 5-1/2. PUMPED IN 30 SX.
GEL MUD AND 100 SX. CEMENT FROM 300' TO BASE CELLAR.
CEMENTED BY GLOBE CEMENTING COMPANY

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
E. M. HILTON - PRESIDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 22ND day of July, 19 59

My commission expires JANUARY 26, 1963
CARMEN REINHARDT LEIKER Notary Public.

PLUGGING
FILE SEC. 35 T. 22 R. 17W
BOOK PAGE 42 LINE 1

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

COPY


Company: HILTON DRILLING CO.
 Firm: Redetzke No. 2

SEC. 35 T. 22 R. 17W
 SE SE NE

Total Depth. 4215'
 Comm. 12-12-55
 Shot or Traced.
 Comm.
 Resum. 7-28-56

Comm. 12-21-55

County Pawnee KANSAS



USING:
 8" 219'
 5" 4213'

Elevation. 4053' DF

Production. 38 BOPD

Figure 1. Late Section of formations

sand, shale	219
shale, red rock	485
shale, sand, red rock	1095
anhydrite	1120
shale, shells	2175
shale, lime	2430
lime	2518
shale, lime	2780
shale	2880
shale, lime	3375
lime	3662
shale, lime	3720
lime	3990
shale, lime	4054
lime	4152
Conglomerate	4167
lime	4215
Total Depth	

Tops:

Heobner	3591
Brown Lime	3697
Lansing	3707
Sh. Conglomerate	4103
Ch. Conglomerate	4142