

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Pawnee County, Sec. 35 Twp 22 S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines C, SW, SE, SE.

Lease Owner Gulf Oil Corporation

Lease Name F. Jennings Well No. 3

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-17 19 56

Application for plugging filed 1-19 19 56

Application for plugging approved 1-19 19 56

Plugging commenced 1-19 19 56

Plugging completed 1-19 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Dry Hole Depth to top Bottom Total Depth of Well 4250' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1086'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran drill pipe to 4000' and circulated with heavy mud for 45 minutes. Laid down drill pipe, placed HOWCO plug and one - third sack of Cotton seed hulls at 300'. Spotted 20 sacks cement on plug through drill pipe. Filled with mud to 35', placed HOWCO plug and one - third sack of Cotton seed hulls at 35'. Ran 10 sacks of cement on plug which filled hole to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker Drilling Company

Address 2008 Lakin St., Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. W. H. Duley

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley


Box 225, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 56

[Signature] Notary Public.

My commission expires October 26, 1959

JRM:REW



JAN 24 1956 1-24-56  
CONSERVATION DIVISION  
Wichita, Kansas

