

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 35 Twp. 22 Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Colorado Oil Company
Lease Name Boyd Well No. 7
Office Address 915 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 5 19 56
Application for plugging filed January 24 19 69
Application for plugging approved January 27 19 69
Plugging commenced February 8 19 69
Plugging completed February 25 19 69
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production August 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Conglomerate Depth to top 4138 Bottom Total Depth of Well 4240 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None
				5-1/2"	4238'	3389'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4216'. Ran sand to 4180', mixed & dumped 5 sacks cement. Rigged up over 5-1/2" casing, loaded hole. Shot pipe at 3367'. Worked pipe loose and pulled 105 joints. Pumped 20 sacks mud, 5 sacks hulls & 100 sacks cement.

PLUGGING COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address P. O. Box 405, Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
915 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 69

Betty J. McElwain
Notary Public.

My commission expires February 19, 1973

DRILLERS LOG

Boyd No. 7
 Loc: SE SE SW
 Sec: 35-22S-17W
 Pawnee County, Kansas
 Company: Colorado Oil & Gas Corporation
 Contractor: Honaker Drig., Inc.

Comm: 3-15-56
 Comp: 3-26-56
 Rotary Total Depth: 4240
 Casing: 8-5/8" at 244'
 5-1/2" at 4238'

0	70	Sand & Gravel	
70	185	Clay & Shale	
185	245	Blue Shale	8-5/8" casing cemented
245	555	Shale & Red Bed	at 244' with 175 sacks
555	635	Sand	common cement and 3
635	1100	Red Bed & Shale	sacks calcium chloride
1100	1125	Anhydrite	
1125	1505	Shale & Shells	
1505	1610	Shale & Salt	
1610	1990	Shale & Shells	
1990	4156	Line & Shale	5-1/2" casing cemented at
4156	4177	Chert & Shale	4238' with 175 sacks
4177	4183	Chert & Line	common cement
4183	4240	Chert & Shale	
4240		Total Rotary Depth	

I certify that this is the true and correct copy of
 the above log to the best of my knowledge.


 H. S. Forbes

Subscribed and sworn to before me this 28th day of
 March, 1956.


 Kenneth G. Fischer, Notary Public

My Commission Expires: 6-25-59