


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 35 Twp. 22S Rge. 17 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW SE NE
Lease Owner Halliburton Oil Producing Co.
Lease Name Redetzke #1 Well No. _____
Office Address Stafford, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/26/79 _____ 19____
Plugging completed 7/7/79 _____ 19____
Reason for abandonment of well or producing formation
depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4270'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	327	none
				4 1/2"	4270	2758'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bled gas off casing, surface had water on it. Allied pumped mud in surface to kill water. Sanded hole and ran 4 sacks cement. Shot pipe at 3401', 3305', 3177', 3081', mud came in. Had to get Allied to pump mud out of casing. Shot pipe at 2990', 2895', 2798', 2701', pulled 56 joints. Allied pumped 35 sacks gel at 1000', pulled to 584' and pumped 70 sacks cement. Pulled to 288' and pumped 50 sacks cement. Pulled to 60' and pumped 25 sacks cement. Tallied pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 79

My commission expires



[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1979

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Company: HALLIBURTON OIL PRODUCING COMPANY
 Contractor: MERCKLE DRILLING COMPANY
 Lease: Redetzke #1 Commenced: 4-3-79
 Location: NW SE NE 35-22S-17W Completed: 4-12-79
 Pawnee County, Kansas
 Casing: 8-5/8" @ 327' w/225 sx.
 4-1/2" @ 4270' w/150 sx.

.....

0 - 230'	Surface soil and shale
230 - 330'	Shale and sand
330 - 1104'	Sand and shale
1104 - 1130'	Anhydrite
1130 - 1375'	Shale and shells
1375 - 2031'	Shale
2031 - 3780'	Shale and lime
3780 - 4270'	Lime
4270'	Rotary T.D.

RECEIVED
 STATE CORPORATION COMMISSION

JUN - 8 1979

CONSERVATION DIVISION
 Wichita, Kansas