

1 070297

FEB 10 1987

API NUMBER 15-083-20,578-0000 *OK*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 NW NW, SEC. 30, T 22 S, R 23 W/E

4620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Hays "B" Well # 2

Operator: Edmiston Oil Co., Inc.

County Hodgeman *150.35*

Name & Address 1260 KSB Building

Well Total Depth 4626 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:15 p.m. Day: 10 Month: 2 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4622' Open hole

1st plug sand back to 4570' and pump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Paul Luthi and Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 10 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4570' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 200 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Recovered 2807' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable) observe this plugging.

STATE CORPORATION COMMISSION

DATE 2-18-87

FEB 17 1987 Dan Anderson
(TECHNICIAN)

INV. NO. 16146

2-17-87

CONSERVATION DIVISION
Wichita, Kansas