

To: 1 060054
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

9-8

API NUMBER 15- 083-20,928-0000

NE NE NE, SEC. 27, T 22 S, R 23 W XX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4058

Lease Name Marvin M Well # 1

Operator: American Warrior, Inc.

County Hodgeman 148.95

Name:
Address P.O. Box 399

Well Total Depth 4583 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 467, Chase, KS 67524 9-15-97

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 9 Year: 1997

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage (phone) 316-938-2943

Work: 5 1/2" at 4568' w/100 sx cement, PBD 4583', Open hole

1st plug sand back to 4500' and dump 5 sx cement on top of sand through bailer,

2nd plug at 700' with 80 sx cement,

3rd plug at 320' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 8 Month: 9 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4489' and dumped 5 sx cement on top of sand through bailer,

2nd plug at 700' with 80 sx cement,

3rd plug at 320' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 320' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 9-16-97

Signed Michael Maier (TECHNICIAN)

INV. NO. 49007