

1 080475

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,226-0000

NE SW NW, SEC. 36, T 22 S, R 17 W/EX

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name Crane Well # 1-36

Operator: Boger Brothers Drilling

County Pawnee 138.45

Name & Address P. O. Box 723

Well Total Depth 4260 Conglomerate feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling License Number 9421

Address P. O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 7:00 pm Day: 17 Month: January Year: 19 86

Plugging proposal received from Dale Smith

(company name) Boger Brothers (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1100-1120'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plug water well from bottom to top with cement  
Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 pm Day: 17 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1105' with 50 sx cement, 2nd plug at 460' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement. Plugged water well

with 5 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 27 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

INVOICED

(Do not) observe this plugging.

DATE FEB 5 1986

Signed J. H. Metz (TECHNICIAN)

INV. NO. 12327

MAR 07 1986

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10-4-85 month day year

API Number 15-145-21, 226-0000

OPERATOR: License # 9421 Name Boger Bros. Drlg Address P. O. Box 723 City/State/Zip Great Bend, Ks 67530 Contact Person Mark Boger Phone 316-792-8151

NE SW NW Sec 36 Twp 22 S, Rg 17 West 3630' Ft. from South Line of Section 4290' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9421 Name Company Tools (Boger Bros.) City/State Great Bend, Ks 67530

Nearest lease or unit boundary line 990' feet

County Pawnee

Lease Name Crane Well # 1-36

Ground surface elevation 2054 feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD X Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Surface pipe by Alternate: 1 X 2

Depth to bottom of fresh water 100'

Depth to bottom of usable water 400'

Surface pipe planned to be set 400'

Projected Total Depth 4200' feet

Formation Conglomerate

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9-20-85 Signature of Operator or Agent [Signature] Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 1 2

This Authorization Expires 3-23-86 Approved By 943-85

Speed 1-10-86 400' 2518

Dale Smith called Plug down in 1-23-86

PUSHER CONNIE TD 4260' FORMATION Calcumite SURFACE PIPE 8 7/8" @ 430 w/ 250 rd ANHYDRITE 1100 ELEVATION 2057 KB 1-17-86 7:00 PM STARTING TIME & DATE 1-17-86 9:30 PM COMPLETION TIME & DATE 11:05 (182) 50 SX 1st PLUG @ 1105 FT. W/ 50 SX Only 50 SX 2nd PLUG @ 460 FT. W/ 50 SX 30' b SP 50 SX 3rd PLUG @ 400 FT. W/ 10 SX 40' 10 SX 4th PLUG @ FT. W/ SX Rat 15 SX RAT HOLE CIRCULATION W/ 1" SX W W - 5 SX MOUSE HOLE CIRCULATION W/ No SX WATER SUPPLY WELL PLUGGED W/ 5 SX TECHNICIAN Bend via phone

5- Circulate well for 10 mins Ball 60/40 w/ 6 g/gal

RECEIVED STATE CORPORATION COMMISSION JAN 27 1986 CONSERVATION DIVISION