

1 050195

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,111 - 0000

C NE NW, SEC. 3, T 22 S, R 16 W

660 feet from N/E section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Baldwin Well # 2

Operator: L. D. Drilling, Inc.

County Pawnee

Name & Address Rt. 1, Box 183B

Well Total Depth 3870 125.78 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 981

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 18 Month: April Year: 19 84

Plugging proposal received from Neal Peticord

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 3867 Open Hole

1st plug sand back to 3810 and dump 5 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and pump an additional 140 sx cement

Maximum pressure 700# and shut in pressure 600#

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 pm Day: 18 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3867' Open Hole

1st plug sand back to 3810' and dump 5 sx cement on top of sand, 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8"

rubber plug and pump and additional 140 sx cement.

Maximum pressure 700# and shut in pressure 600#

Remarks: They recovered 3009' of 5 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Halliburton (if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 4-20-84

APR 20 1984

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 1193 4-18

CONSERVATION DIVISION Wichita, Ks.