

3021417

API #. 15-207-19008-0000

TO: 1-21 API NUMBER 15-  
 STATE CORPORATION COMMISSION NW, SEC. 27, T 25 S, R 17 E  
 CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE  
 WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE  
 WICHITA, KANSAS 67202 LEASE NAME MOON/BENNETT WELL # 0  
 TECHNICIAN'S PLUGGING REPORT COUNTY WOODSON  
 OPERATOR LICENSE # 101 WELL TOTAL DEPTH APPROX. 800' FEET  
 OPERATOR: STATE OF KANSAS PRODUCTION CSG: SIZE \_\_\_\_\_ FEET \_\_\_\_\_  
 NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 7" FEET N/A  
 ADDRESS \_\_\_\_\_  
 ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_  
 PLUGGING CONTRACTOR K.W. WELL SERVICE LICENSE NUMBER 3097  
 ADDRESS 19450 FORD RD., CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 1:00PM DAY: 21 MONTH: 1 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2" CASING AT 600', 500' AND AT 250'. THE WELL WAS TO BE CIRCULATED FULL OF CEMENT INSIDE AND OUTSIDE THE 4 1/2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ X \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 4:00PM DAY: 21 MONTH: 1 YEAR: 98

ACTUAL PLUGGING REPORT THE 4 1/2" CASING WAS PERFORATED AT 600', 500' AND AT 250'.

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 650'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 4 1/2" ANNULUS AND ALSO THE 4 1/2" AND 7" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGES AND DISPLACEMENT WERE FILLED FROM SURFACE. 98 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS: Control # 19980029-015  
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel  
 (TECHNICIAN) FORM CP-2/3

2-2-96