

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-075-10066-000

LEASE NAME H C U

WELL NUMBER 2011

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. C  
office within 30 days.

NW SE Ft. from S Section Line  
\_\_\_\_\_ Ft. from E Section Line

LEASE OPERATOR Ladd Petroleum Corporation

SEC. 20 TWP. 21S RGE. 41W (E) or (W)

ADDRESS 40 Village Plaza Liberal, Kansas 67901

COUNTY Hamilton

PHONE# 816 ) 624 - 5227 OPERATORS LICENSE NO. 6029

Date Well Completed \_\_\_\_\_

Character of Well \_\_\_\_\_

Plugging Commenced 11-12-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-14-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Winfield Depth to Top 2768 Bottom 2775 T.D. 2811

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	122	none
				4 1/2	2791	1080

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 1 sk. of hulls @ 2775 to 2520 Pump 50 sks. of cement @ 1100 to 1200  
Pump 40 sks. of cement @ 500 to 400 Pump 40 sks. of cement @ 150 to 50  
Put 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547


Address Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. Brown

(Address) \_\_\_\_\_



SUBSCRIBED AND SWORN TO before me this 20 day of December, 19 85

Kathryn Johnson

My Commission Expires: 10-23-89 Notary Public  
Kathryn Johnson

DEC 23 1985

Form CP-4  
Revised 08-84

12-23-85

CONSERVATION DIVISION  
Wichita, Kansas

LEASER: UNIT NO. 2011  
 OWNER: LEVINGSOON OIL COMPANY  
 CONTRACTOR: EARL P. WAKEFIELD  
 COLL: 10-4-63  
 COMP: 10-7-63

LOCATION: NW SE  
 SECTION 20-21S-41W  
 HAMILTON COUNTY, KANSAS  
 CASING: 8 5/8" Set at 122'  
 & 1 1/2" Set at 2798'

Surface Clay and Sand	128
Blue Shale	628
Shale	1310
Shale and Streaks Anhydrite	1520
Shale and Anhydrite	1695
Salt	1755
Anhydrite and Shale	1780
Salt	1860
Shale and Anhydrite	2235
Shale	2340
Cinarron Anhydrite	2361
Shale and Anhydrite	2410
Shale and Lime	2690
Lime and Shale	2798
END	2798

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log on the UNIT NO. 2011 well, located NW SE of Section 20-21S-41W, Hamilton County, Kansas.

EARL P. WAKEFIELD

BY Earl P. Wakefield

Subscribed and sworn before me this 15 day of October, 1963.

My commission expires:  
January 25, 1965

Wanda W. Riley  
 WANDA W. RILEY NOZARY

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 15 1963

CONSERVATION DIVISION  
 Wichita, Kansas