


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.083.00178.00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 26 Twp. 23 Rge. 21 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW NW SW

Lease Owner L. C. Smitherman Oil Producer

Lease Name Tubbs Well No. 1 # A

Office Address Box 627 - Augusta, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-5 19 56

Application for plugging filed 5-5 19 56

Application for plugging approved 5-5 19 56

Plugging commenced 5-5 19 56

Plugging completed 5-5 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4820 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Water	4007		8 5/8	407'	
Douglas	"	4035				
Base of K.C. Lime	"	4463				
Conglomerate	"	4624				
Mississippi	"	4709				
Gilmore City	"	4800				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud. Halliburton plug set @ 400' cemented with 25 sacks cement. Filled with mud. Halliburton plug set @ 40' cemented with 10 sacks cement to top of hole.

5-19-56

STATE CORPORATION COMMISSION
MAY 12 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company

Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
George R. Dent (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Dent

Box 627 Augusta, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 1956

Kerth H. Carter Notary Public.

My commission expires October 23, 1958.

PLUGGING
FILE SEC. 26 T. 23 R. 21W
BOOK PAGE 59 LINE 20

TUBBS #1 A

15.083.00.178.00.00

Company - L. C. Smitherman Oil Producer Location: NW NW SW, Sec. 26-23-21W,
 Contractor - L. C. Smitherman Drig. Co., Hodgeman County, Kansas.
 Commenced - 4-13-56 Elevation:
 Completed - 5-3-56 Casing: 8 5/8" - 407' cemented W/275 Sks.
 Total Depth - 4820'
 Initial Prod. - D & A

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 40	Soil & Shale
40 - 200	Shale
200 - 407	Lime
407 - 610	Clay
610 - 845	Red Bed
845 - 1065	Sandy lime, Sand
1065 - 1150	Shale W/Sandy Lime
1150 - 1315	Sandy Shale & Shells
1315 - 1460	Shale - Lime & Red Bed
1460 - 1492	Shale, Red Bed W/Lime
1492 - 1700	Shale, Lime Strks.
1700 - 1915	Shale & Shells
1915 - 2085	Shale, Lime, Red Bed
2085 - 2335	Shale, Lime Strks.
2335 - 2495	Shale & Lime
2495 - 2595	Lime
2595 - 2650	Shale & Lime
2650 - 2720	Lime & Shale
2720 - 2795	Shale & Lime
2795 - 2849	Lime & Shale
2849 - 2870	Lime
2870 - 2935	Shale & Lime
2935 - 3065	Lime & Shale
3065 - 3235	Shale & Lime
3235 - 3295	Lime & Shale
3295 - 3505	Shale & Lime
3505 - 3575	Lime & Shale
3575 - 3724	Shale W/Lime
3724 - 4161	Lime & Shale
4161 - 4178	Lime, Chert & Shale
4178 - 4203	Lime & Shale
4203 - 4230	Lime
4230 - 4281	Lime & Shale
4281 - 4344	Lime & Shale W/Brks.
4344 - 4627	Lime
4627 - 4664	Lime W/Shale
4664 - 4728	Lime (Mississippi)
4728 - 4763	Lime & Chert
4763 - 4805	Chert & Lime & Shale
4805 - 4820	Lime & Chert
4820 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Tubbs #1A, located in the NW NW SW of Section 26-23-21W, Hodgeman County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY, INC.
STATE OF KANSAS

MAY 19 1956
REGISTRATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 16th day of May, 1956.

Kurt H. Carter
Notary Public

My commission expires October 23, 1958.

PLUGGING
FILE SEC. 26 T. 23 R. 21W
BOOK PAGE 59 LINE 20