

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 22 Twp. 23S Rge. 22W(E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner Phillips Petroleum Company

Lease Name Querbach Well No. 1

Office Address Box 287, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 12-13-63 19

Application for plugging filed 12-14-63 19

Application for plugging approved 12-14-63 19


Plugging commenced 12-14-63 19

Plugging completed 12-14-63 19

Reason for abandonment of well or producing formation —

If a producing well is abandoned, date of last production — 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, Sublette, Kan.

Producing formation Mississippi Depth to top 4492 Bottom — Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LKC	Dry	3907	4243	8-5/8"	237'	None
Marmaton	"	4250				
Cherokee	"	4424				
Miss	"	4492				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from — feet to — feet for each plug set.

Hookwall pkr was set at 4355, bottom pkr 4148, bottom of top pkr 4107, top of top pkr at 4102. Spotted 25 sx common cmt at 700' and 25 sx at 240', mud to 40' and 1/4 sack hulls and Howco plug at 40', 15 sx cmt to surface. Well P&A 6:45 p.m. 12-14-63.

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1963

CONSERVATION DIVISION
Wichita, Kansas

12-19-1963

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

M. E. Michael Dist. Supt (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael

Box 287, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 63

My commission expires 11-18-65 Joseph M. Neal Notary Public.



WELL LOG

15. 083. 10200.00.00

COMPANY Phillips Petroleum Company

SEC. 22 T. 23S R. 22W

FARM Querback

NO. 1

LOC. C SE SW


TOTAL DEPTH 4700'

COUNTY Hodgeman

COMM. 11-27-63

COMP. 12-14-63

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 243' w/205 sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 245' Surface Soil, Sandstone, Clay and Post Rock
- 480' Shale and Shells
- 750' Red Bed
- 850' Red Bed and Shale
- 960' Sand
- 1370' Shale
- 1420' Anhydrite
- 2175' Shale and Shells
- 2450' Lime and Shale
- 2805' Lime
- 3170' Lime and Shale
- 3340' Chalky Lime and Shale
- 3470' Shale and Lime
- 3560' Lime and Shale
- 3705' Chalky Lime and Shale
- 3785' Lime and Shale
- 4485' Lime
- 4520' Lime and Chert
- 4541' Lime, Shale and Chert
- 4572' Chert and Lime
- 4677' Lime and Chert
- 4700' Chert
- 4700' RTD

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1963

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Querback #1 well.

Subscribed and sworn to before me this 17th day of December 19 63.

My Commission Expires: September 23rd, 1967

NOTARY PUBLIC