

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 10 Twp. 23S Rge. (E)23 (W)

Location as "NE/CNW%SW%" or footage from lines C NW NW

Lease Owner Rains & Williamson Oil Co.

Lease Name HUBIN Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date completed 11-28 1963

Application for plugging filed 11-28 1963

Application for plugging approved 11-28 1963


Plugging commenced 11-28 1963

Plugging completed 11-28 1963

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities

If a producing well is abandoned, date of last production --- 19---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4782 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	590'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet for each plug set.

Spotted 25 sacks cement at 700' and 25 sacks cement at 480'.
Filled hole with rotary mud to 40' of base of cellar. Set
plug and hulls and capped with 15 sacks cement. Plugging
completed at 6:30 P.M., November 28, 1963.

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1963

CONSERVATION DIVISION
Wichita, Kansas

12-4-1963

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains, Partner (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza-Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 1963

My commission expires November 8, 1966

Sherry Gish Notary Public.

15.083.10221.00.00

ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.
#1 HUBIN, C NW NW
Section 10-23S-23W
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
COMMENCED: 11-15-63
COMPLETED: 11-28-63

Remarks: Set 8-5/8" casing at
590' w/265 sacks cement.

Formations:

Clay and Rock	70'
Shale	190'
Sand	220'
Shale	870'
Anhydrite	885'
Shale	930'
Dakota Sand	1140'
Shale	1415'
Red Bed and Shale	1475'
Anhydrite	1500'
Shale and Shells	1855'
Shale and Lime	2445'
Lime and Shale	2990'
Shale and Lime	3985'
Lime and Shale	4055'
Lime	4105'
Lime and Shale	4160'
Lime	4280'
Lime and Shale	4395'
Lime	4594'
Lime and Shale	4603'
Lime	4675'
Lime and Shale	4755'
Lime and Chert	4782'
Rotary Total Depth (D&A)	4782'


We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.



Wilson Rains
Partner

Subscribed and sworn to before me,
a Notary Public in and for the State
of Kansas, County of Sedgwick, this
3rd day of December, 1963.



Sherry Gish Notary Public

My Commission Expires:
November 8, 1966