


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.083.00144.00.00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 3 Twp. 23 Rge. 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines C. NE/4. NW/4
Lease Owner Mack Oil Co.
Lease Name Bristow Well No. 1
Office Address 811 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-14 1961
Application for plugging filed 1-14 1961
Application for plugging approved 1-14 1961
Plugging commenced 1-14 1961
Plugging completed 1-14 1961
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation None Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand and Shells	Water	0	200	8 5/8	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 240'. Set HOWCO plug and hull at 240' with 25 sacks cement from 240' to 165'. Filled with mud to 35'. Placed HOWCO plug and hulls at 35'. Filled to surface with 10 sacks cement.

1-31-61

RECEIVED
JAN 31 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mack Oil Co.
Address 811 Union Center Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert L. Harris (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Harris
Robert L. Harris

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1961

My commission expires September 8, 1963

Eudora Rae Barackman
Eudora Rae Barackman Notary Public.



15.083.00/44.00.00

MACK OIL COMPANY
Duncan, Oklahoma

DRILLERS WELL LOG

Bristow #1

C NE NW Sec. 3-23S-23W
Hodgeman County, Kansas
Elevation: 2238 K.B.
Initial Production: Dry
Contractor: Mack Oil Co.

Commenced R.D. 12-28-60
Completed R.D. 1-12-61
Total Depth: 4810'

Casing Record: 258' 8 5/8" O.D. Surface Casing

<u>STRATA</u>	<u>DEPTH</u>
Clay and Sand	0 - 80
Clay and Shells	80 - 200
Shells and Shale	200 - 262
Clay	262 - 500
Sand	500 - 535
Redbed and Sand	535 - 930
Redbed and Shale	930 - 1846
Shale and Shells	1846 - 2200
Shale and Lime	2200 - 2338
Lime	2338 - 2860
Lime and Shale	2860 - 3613
Lime	3613 - 4500
Chert	4500 - 4512
Lime and Chert	4512 - 4650
Chert	4650 - 4694
Chert and Lime	4694 - 4810

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Dallas A. Kirchman

Signed and sworn to in my presence this 18th day of January, 1961, by Dallas A. Kirchman, representative of Mack Oil Company.

Eudora Rae Barackman
Eudora Rae Barackman
Notary Public

My commission expires September 8, 1963.

RECEIVED
STATE OF KANSAS COMMISSIONER
JAN 31 1961