


15.083.10191.00.00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

HODGEMAN County, Sec. 12 Twp. 23 Rge. (E)23 (W)  
Location as "NE/CNW/SW" or footage from lines C SW NW  
Lease Owner PICKRELL DRILLING COMPANY  
Lease Name JARNAGIN Well No. 1  
Office Address 705 4TH NATIONAL BANK BLDG, WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed January 18, 19 63  
Application for plugging filed January 18, 19 63  
Application for plugging approved January 18, 19 63  
Plugging commenced January 18, 19 63  
Plugging completed January 18, 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4632 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	TO	SIZE	PUT IN	PULLED OUT
		8 5/8"	268'	None

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1963  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 250'. Set plug. Cemented with  
20 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 15 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PICKRELL DRILLING COMPANY  
Address 705 4TH NATIONAL BANK BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. SEBITS  
705 4TH NATL BANK BLDG, WICHITA, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of January, 1963

My commission expires June 21, 1966  
Maxine Blackman  
Maxine Blackman Notary Public.

**ROTARY DRILLING LOG**

*15.083.10191.00.00*

COMPANY: **PICKRELL DRILLING COMPANY**  
 705 4th Natl Bk Bldg  
 Wichita, Kansas  
 LOCATION: Jarnagin  
 C SW NW 12-23S-23W, Hodgeman County, Kansas

Rotary Drilling Commenced 1-6-63  
 Rotary Drilling Completed 1-18-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

CASING RECORD (8 jts) 8 5/8" Surface Casing set at 268', cemented with 180 sacks cement. Circulated. Completed 4:30 P.M. 1-6-63. No oil string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Top Soil	<u>C.F.S.</u>
150	Clay	4440
268	Blue Shale	4537
475	Blue & Black Shale	4555
770	Red Bed	4565
790	Blaine	4632
1050	Sand	
1395	Red Beds, Shale	
1430	Anhydrite	<u>Slope Tests</u>
1705	Red Bed & Shale & Shells	2600
2075	Shale & Lime Shells	3100
2150	Lime & Shale	4150
2970	Lime	
3610	Lime & Shale	
3705	Lime	<u>S.L.M.</u>
3805	Lime & Shale, Sandy	3381
3910	Lime & Shale	3863
4346	Lime	4225
4425	Lime & Shale	
4495	Fort Scott Lime	
4517	Cherty Conglomerate	
4531	Chert	
4537	Mississippi	
4543	Conglomerate	
4549	Mississippian Lime	
4555	Dolomite	
4632	Mississippian - TD	

**RECEIVED**  
 STATE CORPORATION COMMISSION

JAN 28 1963

CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**

By *C. W. Sebits*  
 C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 24th day of January, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

*Maxine Blackman*  
 Maxine Blackman Notary Public