


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 12 Twp. 23S Rge. (E) 23(W)
Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner Pickrell Drilling Company
Lease Name Jarnagin Well No. 2
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 16, 1964
Application for plugging filed August 16, 1964
Application for plugging approved August 16, 1964
Plugging commenced August 16, 1964
Plugging completed August 16, 1964
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4574 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 250'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 3 1964
9-3-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Building, Wichita, Kansas
(Address)

Subscribed AND Sworn to before me this 25th day of August, 19 64

My commission expires August 25, 1964

Maxine Blackman
Notary Public.

15.083.10192.00.00

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Building
Wichita, Kansas

Rotary Drilling Commenced 8-3-64

Rotary Drilling Completed 8-16-64

LOCATION: Jarnagin No. 2, C SE SW Section 12-23-23W, Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (14 jts) 8 5/8" surface casing set at 255', cemented with 170 sacks cement. Circulated. Completed 8:00 P.M. August 3, 1964.
No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

150	Clay & Shale	<u>C. F. S.</u>
185	Sand	4465
255	Blue Shale	4516
535	Shale & Sand	4527
810	Red Beds	4545
825	Blaine	4550
890	Shale, Shells & Red Bedsq	4554
1115	Sand	4559
1425	Shale & Shells	4566
1460	Anhydrite	4574
2215	Shale & Shells	
2360	Lime & Shale	<u>Slope Test</u>
2755	Lime	2550
3505	Shale & Lime	3075
3695	Sandy Lime & Shale	3610
4527	Lime	4330
4545	Conglomerate	
4550	Lime	
4574	Mississippi - RTD	<u>S. L. M.</u>
		3668
		3994
		4278

RECEIVED
STATE CORPORATION COMMISSION


SEP 3 1964

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By *C. W. Sebitts*
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:



On this 25th day of August, 1964, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966.

Maxine Blackman
Maxine Blackman Notary Public