

15.083.10336.00.00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 14 Twp 23S Rge. (E) 23 (W)
Location as "NE/CNW%SW%" or footage from lines 300' S of Ctr SW NW
Lease Owner Texaco Inc.
Lease Name E. F. Lippoldt Well No. 5
Office Address 614 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-16-19 64
Application for plugging filed (8-19-64) Attached 19
Application for plugging approved Verbal 19
Plugging commenced 8-16-19 64
Plugging completed 8-16-19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4582 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| Dry Hole | | | | 8-5/8" | 295' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 4582-290 w/mud
290-240 w/cmt
240-40 w/hvy mud
40-5 w/cmt
5-0 w/clay.

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address 352 North Broadway, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. N. Wade (employee of owner)

That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. N. Wade
614 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 64


My commission expires 6-20-68 A. E. Boyd Notary Public.

Company- TEXACO
Farm- Lippoldt No. 51

SEC. 14 T. 23 R. 23W
C SW NW

Total Depth. 4532'
Comm. 7-30-64 Comp. 8-15-64
Shot or Treated.
Contractor. Garvey Drilling
Issued. 12-19-64

County Hodgeman
KANSAS



CASING:

8 5/8" 295' cem w/ 225 sx

Elevation. 2296' KB

Production. Dry

Figures indicate Bottom of Formations.

| | |
|----------------------------|----------|
| surface soil | 20 |
| surface clay & sand | 175 |
| sand | 272 |
| blue shale | 295 |
| shale | 560 |
| red bed | 795 |
| anhydrite | 825 |
| shale & sand | 1425 |
| anhydrite | 1460 |
| shale & shells | 1776 |
| shale w/ lime strks | 2155 |
| shale & lime | 2355 |
| lime | 3015 |
| lime & shale | 3145 |
| shale & lime streaks | 3305 |
| shale & lime | 3385 |
| lime & shale | 3410 |
| shale & lime w/ chalk stks | 3545 |
| shale, lime & chalk | 3685 |
| lime & shale | 3895 |
| lime | 4435 |
| lime & shale | 4475 |
| lime | 4504 |
| core | 4582 RTD |
| Total Depth | |

TOPS: SCOUT

| | |
|-------------------|------|
| Heebner | 3822 |
| Toronto | 3837 |
| Lansing | 3887 |
| Marmaton | 4304 |
| Fort Scott | 4420 |
| Mississippi | 4513 |
| Mississippi Osage | 4550 |

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1966

WICHITA, KANSAS