

4-060574

8-17

15009150690000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 7-23-40
180' N. of

SE SE NE /4 SEC. 30 , 16 S , 11 W
3150 feet from S section line
330 feet from E section line

Operator license# 4058

Lease Esfeld well # 2

Operator: American Warrior, Inc.

County Barton

Address: P.O. Box 399
Garden City, Kansas 67846

Well total depth 3117 feet ^{101.30}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 395 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 9:00A.M. Day: 17 Month: August Year: 94

Plugging proposal received from: Dean Ives

Company: American Warrior, Inc. Phone: 316-275-2963

Were: Order 285 sxs. 60/40 posmix - 10% gel and hulls.
200' of fluid in bottom of hole with perms open.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:15A.M., Day: 17, Month: August, Year: 94

Actual plugging report: 8 5/8" to 395'. 5 1/2" to 3035' w/100 sxs.
Perforate at 410' - 790' - 1475'. Tied onto casing and pumped 270 sxs.
cement with 500# hulls. Max. 1000#. S.I.P. 200#. Tied annulus and
pumped 30 sxs. cement. Max. 200#. S.I.P. 75#. 08-19-94 cement down
30 feet.

Remarks: Halliburton Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1908 GL

I did X (did not) X observe the plugging.

[Signature]
DH (agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1994
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
DATE AUG 29 1994
INV. NO. 41047