

21

6 062313

15-009-30403-0001-32
E-13-453

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-13-453
NE, SEC. 30, T 16 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

3960 feet from S section line
1320 feet from E section line

Operator License # 4058

Lease Name Esfeld Well # 10

Operator: American Warrior Inc.

County Barton 107.64

Name & Address Box 399

Well Total Depth 3312 feet

Garden City, Ks. 67846

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 734

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number

6050

Address box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00 AM Day: 22 Month: Jan Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 50 sks common 350 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 12:15PM Day: 22 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT 10 3/4 set at 743 w/770 sks. 7" set at 3312 w/150 sks.

top perf at 2965. Plugged bottom w/sand and 7 sks cement to 2900. Pumped in 7"

50 sks common cement followed w/150 sks of 60/40 poz w/8% gel followed w/300 sks cement

w/1200 psi. 10 3/4 50 sks cement w/550 psi.

STATE 1-28-91

IAN 28 1991

Remarks: By Halliburton Shot hole at 750. Ran line to 3000.

INVOICED

(if additional description is necessary, use BACK of this form.)

DATE 2-8-91 observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN)

INV. NO. 30629