

To: 6 062314
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-02090000 13A
NE, SEC. 30, T. 16 S, R 11 W&B

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior Inc.
Name & Address Box 399
Garden City, Ks. 67846

4290 feet from S section line
1980 feet from E section line
Lease Name Esfeld Well # 7
County Barton 108.74
Well Total Depth 3346 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 353

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00 AM Day: 22 Month: Jan Year: 19 91

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943
were: Order 300 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:50PM Day: 22 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8 set at 353 w/150 sks. 5 1/2 set at 3287 w/125 sks.
Top perf at 2965. Plugged bottom w/sand and 5 sks cement to 2900.
Pumped in 5 1/2 25 sks cement followed w/5 sks hulls in 225 sks cement
w/900 psi. 8 5/8 50 sks cement w/350 psi.

Remarks: by Halli burton Shot hole in 5 1/2 at 750.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-8-91
INV. NO. 30627

Signed Gilbert G. Scheck
GILBERT GIESON & GRAN E.A.G.