

To: 1 051929.  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

6-26

15-075-20001-8000  
API NUMBER 15- Docket #D-13,836  
C NW SE, SEC. 19, T 21 S, R 41 W/E

13

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_  
Operator: Kansas Corporation Commission  
Name: \_\_\_\_\_  
Address: 130 S. Market, Rm. 2078  
Wichita, KS 67202-3802

1980 feet from S section line  
1980 feet from E section line  
Lease Name R. Statts Well # 1  
County Hamilton  
Well Total Depth 2830 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 355

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 10:30 a.m. Day: 26 Month: 6 Year: 19 95

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-225-6760

were: 4 1/2" at 2830', 2 1/16" at 1490' with 700 sx cement circulated to surface  
4 1/2" perforated at 2758-76'.

1st plug pump down 2 1/16" tubing with 15 sx cement,

2nd plug pump down 4 1/2" casing with 200 lbs. hulls, 115 sx cement with 100 lbs. hulls mixed in.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 26 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 2 1/16" tubing with 15 sx cement.  
Maximum pressure 500 psi and shut in 250 psi.

2nd plug pumped down 4 1/2" casing with 200 lbs. hulls, then pumped 115 sx cement with 100 lbs. hulls mixed in. Pressured to 1000 psi, shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)