

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-24028-00.00

NW 1/4 Sec. 26, T 23 S, R 24 W/E

2310 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name G. 663 Well # 1

Operator: Beron Corporation  
Name & Address 970 1/4 Financial Center  
Wichita, KS 67202

County Hodge man

Well Total Depth 4769 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 569' 380 sy

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Strata Drilling License Number 2188 Tag 66

Address 6200 + Bond Rd 67530

Company to plug at: Hour: 4:00 pm Day: 1 Month: Jan Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Chin

(company name) Strata Drilling (phone) 793.7456

were: Heavy mud to 1350' bit. 70 sy cement at 1350' mud  
to 470' H/S cement mud to 40' solid bridge 10 sy cement  
to Surf Face 10 sy cement in rat hole 50-56 per 119 gal  
39 cc.

Signed J. M. Zief (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 pm Day: 2 Month: Jan Year: 19 83

ACTUAL PLUGGING REPORT

70 sy cement at 1350'  
40 sy cement at 470'  
10 sy cement at 40' solid bridge  
10 sy cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 04 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cement by Halliburton

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ did not) observe this plugging.

INVOICED  
1-13-83  
2129-W

Signed J. M. Zief (TECHNICIAN)

\$ 154.99

RECEIVED

NOV 10 1954

1954

THE UNIVERSITY OF MICHIGAN LIBRARY

ANN ARBOR

1954