

15-097-21127-06-01

API NUMBER 15- Docket #D-25,622

W/2 NW SE, SEC. 3, T 28 S, R 16

1980 feet from S section line

2310 feet from E section line

Lease Name Light Well # 1

County Kiowa

Well Total Depth 4820 156.65 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well Gas Well Input Well SWD Well X O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:15 a.m. Day: 21 Month: 6 Year: 1994

Plugging proposal received from Vernon Duntz, Jr.

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

Perfs: 4 1/2" at 4819' w/150 sx cement, Perfs at 4154-59, 4636-42, 4654-60, 4679-85, 4709-16'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 a.m. Day: 21 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 6-27-94

INV. NO. 40633

Signed Stephen J. Pfeiffer (TECHNICIAN)

FORM CP Rev. 1

To: 1 040858 6-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317

Operator: Continental Energy

Name & Address P.O. Box 918

Garden City, KS 67846

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1994  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 6-27-94

INV. NO. 40633

6-21