

1 080271

API NUMBER 15-097-20,529 - 0000 *R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SE NE       , SEC. 3, T 28 S, R 16 W/~~X~~

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Harper Well # 1-3

Operator: Imperial Oil Company

County Kiowa 152.91

Name & Address 720 4th Financial Center

Well Total Depth 4705 feet

Wichita, KS 67202

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 30 Month: November Year: 19 84

Plugging proposal received from Joe Maes

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4705' Perfs at 4623-29' PBTD 4660'

1st plug pump 2 sx hulls and 30 sx cement to bottom and stop plug at 4000'

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45 pm Day: 30 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4705' PBTD 4660' Perfs at 4623-29'

1st plug pumped 2 sx hulls, 30 sx cement to bottom and stopped plug at 4000', 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and

125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 250 psi

12-5-84  
Rec' 2200'  
DEC 05 1984  
J. Cassidy  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED  
(attach) observe this plugging.

12-12-84

Signed J. H. Metz  
(TECHNICIAN)

NO. NO. 5902