

1 090084

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,487-0000

C SW , SEC. 3 , T 22 S, R 40 W/E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3691

Lease Name Heinz Well # 1

Operator: Brock Resources, Inc.

County Hamilton 91.65

Name & Address

Well Total Depth 2820 feet

25th & Vine St.

Conductor Pipe: Size feet

Dean Ellner Bldg., Suite 2

Surface Casing: Size 8 5/8 feet 228

Hays, KS 67601

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 30 Month: 5 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 2819' w/110 sx cement, PBTD 2795', Perfs at 2732-43'

1st plug spot 20 sx cement on bottom,

2nd plug at 1175' with 50 sx cement,

3rd plug at 240' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:20 p.m. Day: 30 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to 2550',

2nd plug pulled to 1050', spotted 50 sx cement,

3rd plug pulled to 240', spotted 50 sx cement,

4th plug pulled to 40', spotted 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 07 1991

CC. CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Sargent's. Recovered 2323' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

(if necessary) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 6-17-91

INV. NO. 32151

5-30