

1060173

TO:
STATE CORPORATION COMMISSIONAPI NUMBER NA 15-083-10134-00-01
SE NW SE SEC. 15, T 22 S, R 25 WCONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINEWICHITA, KANSAS 67202 LEASE NAME HALLET WATERFLOOD (LARKIN) WELL # 2TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMANOPERATOR LICENSE # 3273 WELL TOTAL DEPTH 5300 FEETOPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 5 1/2" @ 4709' WITH 450 SXNAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 475' WITH 500 SXADDRESS LAWRENCEVILLE, IL 62439ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR CHEYENNE WELL SERVICE LICENSE NUMBER 6454ADDRESS PO BOX 384 NESS CITY, KS 67560-0384COMPANY TO PLUG AT: HOUR: 10:40 AM DAY: 22 MONTH: 09 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM (COMPANY NAME) CHEYENNE WELL SERVICE (PHONE) 316-264-6366WERE: PERFS AT 4594-4606 AND 4616-4636

PROPOSED METHOD OF PLUGGING SAME AS ACTUAL METHOD.

INVOICED

DATE 10-8-99INV. NO. 2000060661PLUGGING PROPOSAL RECEIVED BY MIKE MAIERPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 22 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT BOTTOM PLUG 2400' WITH 50 SX CEMENT & 200# HULLS 2100' OF 2 7/8"
TUBING & PACKER LEFT IN HOLE. LOST TOOL IN TUBING-TUBING ALSO DROPPED TO BOTTOM & COULDN'T
RECOVER. THE WELL HAS BEEN PERFORATED AT 1100' & CEMENT WAS BROUGHT TO 475' TO BOTTOM OF
SURFACE AS INDICATED ON LOG. PULLED TUBING TO 1700' & CIRCULATED TO SURFACE USING 135 SX
CEMENT. PULLED TUBING AND TOPPED OFF WITH 25 SX CEMENT. TIED ON TO BACKSIDE PUMPED 30 SX
CEMENT. PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3