

15-093-10135-0001

Docket #E-7630

To: 1 051096 10-21-88
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 2/12/57

SW NW SE, SEC. 15, T 22 S, R 25 W/E

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Operator: Chevron U.S.A. Inc.

Name &

Address P.O. Box 12116

Oklahoma City, OK 73157

Lease Name Hallett Well # Larkin-3

County Hodgeman 152.10

Well Total Depth 4680 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 561

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 9 a.m. Day: 19 Month: 10 Year: 19 88

Plugging proposal received from Dink Klutts

(company name) Chevron U.S.A. Inc. (phone) 405-949-7000

were: 5 1/2" at 4670' PBSD 4633' Perfs at 4592-97, 4603-10, 4627-31'

1st plug set CIBP at 4552', spot balanced plug from 4542-4342', displace hole with mud,

2nd plug spot cement plug from 1150'-950', test casing to 250 psi, perforate at 571' and

establish circulation to surface up 5 1/2" X 8 5/8" annulus,

3rd plug pump cement down 5 1/2" until cement returns are observed.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:30 p.m. Day: 19 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 4538', pumped 50 sx cement below retainer and 25 sx cement above retainer,

2nd plug filled hole with 9 ppg mud from 4300' to surface, perforated 5 1/2" at 1175' with

2 SPF, set cement retainer at 1100', pumped 50 sx cement below cement retainer into perfs,

Shut in pressure 1200 psi. Pumped 25 sx cement above cement retainer.

3rd plug tested casing to 250 psi. Perforated 5 1/2" at 580', circulated cement down 5 1/2" to 580' and up 8 5/8" to surface, used 200 sx cement.

Remarks: Used Class A cement by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 10-24-88

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 22664

10-19 NOV 15 1988