

1 030152

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10' API NUMBER 15-185-21,978-0000
E N/2
NW SE, SEC. 8, T 22 S, R 12 W
2310 feet from ~~XX~~/S section line
1970 feet from ~~XX~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5053

Lease Name Fischer Well # 1

Operator: Petro-Dynamics Corporation

County Stafford

Name & Address 555 N. Woodlawn Building 1, Ste. 207

Well Total Depth 3760 122.20 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kandrilco, Inc. License Number 5889

Address 555 N. Woodlawn Building 1, Suite 207, Wichita, KS 67208

Company to plug at: Hour: 8:00 am Day: 15 Month: April Year: 19 84

Plugging proposal received from Larry Hicks

(company name) Kandrilco, Inc. (phone) 316-681-1623

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3680' with 25 sx cement

2nd plug at 690' with 50 sx cement

3rd plug at 330' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement, 7th plug to circulate mousehole with 10
sx cement. Plug water well. Plugging Proposal Received by Steve Rount
with 5 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:14 am Day: 15 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3680' with 25 sx cement, 2nd plug at 690' with 50
sx cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with
10 sx cement, 7th plug to circulate mousehole with 10 sx cement, plug water well with
5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc by Allied
(If additional description is necessary, use BACK of this form.)
STATE CORPORATION COMMISSION

INVOICED

(date) (time) observe this plugging.

APR 20 1984

Signed Steve Rount
(TECHNICIAN)

DATE 4-20-84

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 1198 2-15

APR 27 1984