

15.185-11174-0000

To: 1 070036  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-Drilled 4/25/44  
C SW NW, SEC. 8, T 22 S, R 12 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170  
Operator: Globe Operating, Inc.  
Name & Address: P.O. Box 12  
Great Bend, KS 67530

Lease Name Charles Well # 1  
County Stafford 119.57  
Well Total Depth 3679 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 31 Month: 10 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 3674' w/200 sx cement, Open hole

1st plug sand back to 3000' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx gel, 50 sx cement, and 5 sx gel at 690',

3rd plug pump 50 sx cement at 300',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3000' and dumped 5 sx cement on top of sand through bailer,

2nd plug at 690' pumped 5 sx gel, 50 sx cement and 5 sx gel, 11-10-97

3rd plug at 300' pumped 50 sx cement,

4th plug at 40' with 10 sx cement. This plug witnessed by Richard Lacey.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1660' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby observe this plugging.

DATE 10-13-97

Signed [Signature] (TECHNICIAN)

INV. NO. 49488