

10-11

1 040171

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,548-0000
NW NE NE, SEC. 20, T 22 S, R 12 W/E X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Operator: Abercrombie Drilling, Inc.
Name & Address: 801 Union Center
Wichita, KS 67202

4950 feet from S section line
990 feet from E section line

Lease Name Spangenburg Well # 1

County Stafford 120.90

Well Total Depth 3720 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 11 Month: 10 Year: 19 88

Plugging proposal received from Harold Mailey

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 670-90'

1st plug at 3714' with 40 sx cement, 2nd plug at 700' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1 p.m. Day: 11 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3714' with 40 sx cement,

2nd plug at 700' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 10-27-88

REV. NO. 22754

Signed Stephen J. Pfeifer
(TECHNICIAN)