

To: 1 120694 3-3.1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,545-0000

NW SW SW, SEC. 20, T. 22 S, R. 12 W/E

990 feet from S section line

4950 feet from E section line

Lease Name Teichman Well # C-1

County Stafford

Well Total Depth 3807 123.72 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 694

TECHNICIAN'S PLUGGING REPORT

Operator License # 5057

Operator: Voight Oil & Gas Company Inc.

Name & Address Rt. 3, Box 33B

McPherson, KS 67460

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 31 Month: 3 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

logs: 5 1/2" at 3801' w/150 sx cement, PBSD 3486', Perfs at 3474-82'

1st plug sand back to 3434' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 8 sx gel, 50 sx cement, 7 sx

gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 31 Month: 3 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3434' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 8 sx gel, 50 sx cement, 7 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. 4-1-92

Pumping pressure 0-800 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2450' of 5 1/2" (if additional description is necessary, use BACK of this report.)

INVOICED (add to check) observe this plugging.

DATE 4-8-92

INV. NO. 34915

Signed Duane Rankin (TECHNICIAN)

RECEIVED CONSERVATION COMMISSION APR 11 1992