

2-070603
23 R

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

3-20-96

API NUMBER: 15-155-20,479 D-19,368

SE SW SW SEC 17 , T 22 S, R 9W

OPERATOR LICENSE # 100

330 FEET FROM S SECTION LINE

OPERATOR: KS Corporation Commission

4290 FEET FROM E SECTION LINE

NAME & 130 S. Market

LEASE NAME: F Drake WELL # B-7

ADDRESS: Wichita, KS 67202

COUNTY: Reno

WELL TOTAL DEPTH: 4142'

CONDUCTOR PIPE: 5 1/2" @ 3798'

SURFACE CASING: 8 5/8" @ 245'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD D-19,368 RECEIVED
KANSAS CORPORATION COMMISSION

OTHER WELL AS HEREINAFTER INDICATED: _____

APR 16 1996

PLUGGING CONTRACTOR Fee Fund using D S & W

ADDRESS: 403 Front Street, Claflin KS 67525 LICENSE CONSERVATION DIVISION
WICHITA, KS

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 20 MONTH: March YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM Ken Strube

COMPANY NAME: D S & W PHONE: 316-587-3361

WERE: 35 sacks - 2100' 25 sacks - 1250' 25 sacks - 845' 250' to 0

PLUGGING PROPOSAL RECEIVED BY: Dave Wertz

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { x } PART { _____ } NONE { _____ }

COMPLETED: HOUR: 3:00 DAY: 20 MONTH: March YEAR: 1996

ACTUAL PLUGGING REPORT: Ran tubing with bit in to 2050' circulated and turned bit got to 2100' Pumped 35 sacks of cement Pulled tubing to 1250' Pumped 25 sacks pulled to 845' Pumped 25 sacks Pulled to 250' Circulated Cement to surface. Back side was squeezed to surface. Cut off surface pipe - filled everything back as it was.

REMARKS: Allied #1760 60/40 4%

I DID OBSERVE THIS PLUGGING.

Jack Luthi
Jack Luthi AGENT

DW