

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Company

Complete Address: 411 1st Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Koehn Well No. 1

Location C SW SW Sec. 16 Twp. 22 Rge. 15 (E) (W) XX

County Pawnee Total Depth 4059

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: (OWWO)

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 6:30P Day 12 Month 10 Year 1968

The Above well was plugged as follows:

Total depth 4059' 8 5/8 csg set at 243' cwc.

4 1/2 csg set at 4003' cw 100 sc cement.

4 1/2 csg PBTD 3900' top perf. 3864'

Filled 4 1/2 csg with sand (3850-3900) dumped 4 sc cmt with dump bailer. (3800-3850)

Recov. 3575' of 4 1/2 csg.

Pumped thru 8 5/8 plg container with 80 bbl mud, plug and 100 sc 50-50 poz cement with 6% total gel. Max. pres. 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: Geo Massum
Well Plugging Supervisor

INVOICED

DATE 10/14/68
INV. NO. 8623-4