

R

KANSAS

Form CP-3

Rev. 6-4-68

RECEIVED

STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 26 1979

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 145- 20,564-0000 (of this well)

Operator's Full Name Deck Oil Co.

Complete Address Suite 4000, One William, Ctr., Tulsa, Ok. 74172

Lease Name Fertig Well No. 1

Location C W/2 SW NE Sec. 16 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3996'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Gabbert-Jones

Address Wichita, Ks. License No.       

Operation Completed: Hour 10:30 P Day 24 Month 1 Year 1979

The above well was plugged as follows:

RTD 3996' 8 5/8 csg set 270' cwc 200 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 360' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1-30-79

INV. NO. 9034. W