

KANSAS

Form CP-3

Rev. 6-4-68.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 11 1977  
10-11-77  
CONSERVATION  
Wichita, Kan.

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 083 - 20538 - 0000 (of this well)

Operator's Full Name E. K. Edmiston Oil Co., Inc.

Complete Address 800 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Hays "B" Well No. 1

Location NE NE NW Sec. 30 Twp. 22 Rge. (E) (W) 23

County Hodgeman Total Depth 4700'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:15 A Day 6 Month 10 Year 1977

The above well was plugged as follows:

Total Depth 4700' 8 5/8 csg set 330' cwc 320 sx.

4 1/2 csg set 4699' cw 150 sx cem.

4 1/2 csg FBTD 4649' & Perf. (4633-4622)

Filled 4 1/2 csg W/sd (4649'-4600') dumped 3 sx cem W/dump bailer. (4600'-4570')

Cutoff & recovered 2808' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls, followed with 70 sk 50-50 poz 6% -displaced with 7 sk gel & water -capped

with cementing plug & 70 sx 50-50 poz 6% & shutin. FPP 700 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 10-12-77  
# 5984-W

Signed: Geo Massey  
Well Plugging Supervisor