

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

11-12-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name MacDonnell Well No. 1

Location NW NW SW Sec. 36 Twp. 22 Rge. (E) (W) 17

County Pawnee Total Depth 4247'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2 P Day 8 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 4247' 8 5/8 csg set at 253' cwc 175 sk.

5 1/2 csg set at 4246' cw 125 sk cem.

5 1/2 csg PBSD 4231' & perf. (4162-4170)

Filled 5 1/2 csg W/sd (4145-4231) dumped 5 sk cmt W/dump bailer. (4110-4145)

Cutoff and recovered 2517' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk Gel & water W/300 lbs hulls, released plug and

pumped 100 sk comm cem. by Sun Cementing Co. Max FP 100# SIP static.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Thassey
Well Plugging Supervisor

INVOICED

DATE 11/12/73

INV. NO. 8154-U