

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-097-20529-0000

API NUMBER \_\_\_\_\_

LEASE NAME Harper #1-3

WELL NUMBER \_\_\_\_\_

SPOT LOCATION G SE NE

SEC. 3 TWP. 28 SRGE. 16 W(E) of (W)

COUNTY Kiowa

Date Well Completed \_\_\_\_\_

Plugging Commenced 11/15/84

Plugging Completed 11/30/84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Imperial Oil Co.

ADDRESS 720 4th Finan, Ctr. Wichita, Ks. 67202

PHONE # (316) 263-5205 OPERATORS LICENSE NO. 5028

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4705'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	360'	none
				4 1/2"	4705'	2236'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 2 hulls, & 30 sacks cement, plug to 3850'. Shot pipe at 3806', 3545', 3020', 2811', 2605', 2400', & 2236'. Pulled 54 joints of pipe. Plugged well with 2 hulls, 10 gel, 50 cement, 10 gel, 1 hull, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524 12-7-84

RECEIVED

STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso


(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1984



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_