

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20,366-0000

LEASE NAME Shetterly

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION C SW/4

SEC. 10 TWP. 22 SRGE. 40 ~~KXXXX~~ (W)

COUNTY Hamilton

LEASE OPERATOR Dernick Resources, Inc.

Date Well Completed 3-31-81

ADDRESS P. O. Box 6; Liberal, KS 67901

Plugging Commenced 8-15-85

PHONE # (316) 624-3767 OPERATORS LICENSE NO. 7040

Plugging Completed 8-15-85

Character of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City
old well-spudded

Is ACO-1 filed? 2-11-81 If not, is well log attached? on file in Wichita

Producing formation Winfield Depth to top 2725' bottom 2741' T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Winfield.	gas	2725'	2741'	8 5/8"	369'	0
				4 1/2"	2799'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pumped 2 sx hulls, 40 sx 60/40 Pozmix w/ 6% gel, 8 sx gel and 100 sx 60/40 Pozmix w/ 6% gel down 4 1/2" csg. Pressured 0-1300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementers License No. _____
Address N. Highway 283; Ness City, KS 67560

RECEIVED

STATE OF Kansas COUNTY OF Seward, ss. STATE CORPORATION COMMISSION

AUG 20 1985

Terry W. Maxwell (employee of operator) or
(XXXXXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

WICHITA DISTRICT DIVISION
Wichita, Kansas

(Signature) Terry W Maxwell

(Address) P. O. Box 6; Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1985

Edna M. Parish
Notary Public

My Commission expires: 2-19-89

