

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

30100-00-00

API NUMBER 15-075-30101
 LEASE NAME Gould A
 WELL NUMBER 1-6
2530 Ft. from N' Section Line
3300 Ft. from E Section Line
 SEC. 6 TWP. 22S RGE. 40W (E) or (W)
 COUNTY Hamilton
 Date Well Completed 10/10/65
 Plugging Commenced 09/27/00
 Plugging Completed 09/27/00

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P.O. Box 18496, Okla. City, OK 73154-0496

PHONE# (405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/04/2000 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Winfield Depth to Top 2754' Bottom 2754' T.O. 2780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8"	308'	
				4-1/2"	2779'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
MIRU Log Tech, perforate @1150', MIRU Allied, pump 135 sx cmt, max PSI 1000#, SITP 400#,
pump down 8-5/8"x4-1/2" 200 sx cmt, max PSI 400#, SITP 100#, Cut off pipe & cap well.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. STATE OF KANSAS CORPORATION COMMISSION

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc. 10-5-00 RECEIVED

STATE OF OK COUNTY OF OK, ss. CONSERVATION DIVISION
 Wichita, Kansas

Randy Gasaway (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Randy Gasaway
 (Address) P.O. Box 18496, OKC, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 2000

My Commission Expires: 8-24-04
Notary Public

(Handwritten initials)

ALLIED CEMENTING CO., INC. 5253

Federal Tax I.D.# 48-0727880

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

15-075-30100-0000

DATE <u>9-22-00</u>	SEC <u>6</u>	TWP. <u>22 S</u>	RANGE <u>40 W</u>	CALLED OUT	ON LOCATION <u>9:45 AM</u>	JOB START	JOB FINISH <u>NOON</u>
LEASE <u>Gould</u>				WELL# <u>1-6</u>		LOCATION <u>Tribune South to C.L.</u>	
COUNTY <u>Hamilton</u>				STATE <u>Kan</u>			
OLD OR NEW (Circle one)				<u>7 1/2 S - E.S.</u>			

CONTRACTOR None
 TYPE OF JOB OHP
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 800' MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER Same
 CEMENT
 AMOUNT ORDERED 355-sks 60/40 per
6 1/2 gal 200# Hulls

COMMON	<u>213</u>	SKS	@	<u>7.55</u>	<u>1,608.15</u>
POZMIX	<u>142</u>	SKS	@	<u>3.25</u>	<u>461.50</u>
GEL	<u>18</u>	SKS	@	<u>9.50</u>	<u>171.00</u>
CHLORIDE			@		
<u>Hulls</u>	<u>2</u>	<u>sks</u>	@	<u>15.50</u>	<u>31.00</u>
			@		
			@		
			@		
			@		
HANDLING	<u>375</u>	SKS	@	<u>1.00</u>	<u>375.00</u>
MILEAGE	<u>44</u>	<u>per sk/mile</u>			<u>975.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Dalt
 # 191 HELPER Dean
 BULK TRUCK
 # 318 DRIVER Andrew
 BULK TRUCK
 # _____ DRIVER _____

TOTAL 3,640.15

REMARKS:

Mix 200# Hulls + 20 SKS cement w/
100# Hulls, Displace 35 BBL, Pressure
to 1000# Perf @ 1150' max 135 SKS
connect down 4 1/2 @ 200', shut in @
400', mix 200 SKS down Annulus @
300', shut in @ 100'

SERVICE

DEPTH OF JOB	<u>15'</u>	Well
PUMP TRUCK CHARGE	<u>450.00</u>	
EXTRA FOOTAGE		@ _____
MILEAGE	<u>65 miles</u>	@ <u>3.00</u> <u>195.00</u>
PLUG		@ _____
		@ _____
		@ _____

TOTAL 645.00

CHARGE TO: Chesapeake Operating
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@ _____
	@ _____
	@ _____
	@ _____
	@ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE 4,285.40
 DISCOUNT -428.54
= 3,856.86 IF PAID IN 30 DAYS

SIGNATURE Dennis Frick

PRINTED NAME _____