


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 35 Twp. 22S Rge. 25 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
75' E C SE SE

Lease Owner K.R.M. Petroleum Corporation
Lease Name Nuss-Rabe "A" Well No. 1
Office Address 820 Guaranty Bk. Bldg., Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 9/18 19 78
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well 4700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	444'	8-5/8"	11 fts.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug-set. 50 sx. @ 1000', 35 sx. @ 400', 10 sx. @ 40'-0', & 5 sx. in rathole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.

STATE OF Colorado COUNTY OF Denver, ss.
J. C. Simmons (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. C. Simmons
K.R.M. PETROLEUM CORPORATION
820 Guaranty Bank Bldg., Denver, CO 80202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 78

My commission expires 1/22/79

Shirley M. Wegner
Notary Public.
Shirley M. Wegner

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Nuss-Rabe "A" #1
C-SE-SE Sec. 35-22S-25W
Hodgeman County Kansas

Commenced: 9-8-78

Completed: 9-18-78

OPERATOR: KRM PETROLEUM CORP.

From	Depth to	Formation	Remarks
0	270	Clay-Post Rock-Shale	Ran 11 jts of 20# 8.5/8" csg
270	447	Shale	set @ 444' Cemented w/
447	820	Shale-Shells-Sand	275 sks Common 2% Gel
820	1135	Shale-Redbed	3% CC PD @ 11:00 a.m.
1135	1325	Sand	9-8-78
1325	1665	Shale-Redbed	
1665	1676	Anhy	
1676	1800	Shale-Redbed	
1800	4015	Lime-Shale	
4015	4700	Lime	
	4700 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 27th day of September, 1978.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.



RECEIVED
STATE CORPORATION COMMISSION

OCT - 5 1978

CONSERVATION DIVISION
Wichita, Kansas